



## REQUEST FOR PROPOSAL (RFP) CLARIFICATION

### INVITATION OF BIDS FOR REPAIR AND WATERPROOFING OF ROOFTOP AT APS BATHINDA LOCATED AT BATHINDA MIL STATION

1. Based on various queries received from the prospective vendors, following is clarified:-

(a) Page No 7 : Part II para 1 (d) : Complete Water proofing of roof and parapet wall with minimum seven years of guarantee.

(b) Page No 7 : Part II para 2 (b) : **Surface Preparation**. Surface preparation to include pressure wash cleaning to remove all dust, fungus, etc., with pressure washer after repairing the existing roof and parapet having old bitumen membrane by filling cracks, potholes, holes with waterproofing compound.

(c) Page No 8 : Part II para 2 (e) (i) : Treatment of roof and parapet wall with reinforced Elastomeric liquid waterproofing membrane of 400-micron (four coats of 100 micron each) thickness having SRI of 90 and/or above tested as per ASTM E 1980 (with solar Reflectance and Thermal Emittance tested as per ASTM C 1549 and ASTM C 1371, respectively).

(d) Page No 8 : Part II para 2 (e) (iv) : Surface preparation includes pressure wash cleaning to remove all dust, fungus, etc., with pressure washer after repairing the existing roof and parapet wall having old bitumen membrane by filling cracks, potholes, holes with waterproofing compound having compressive strength as per IS:4031 Part-6 1988 and permeability of water as per IS:2645-2003.

(e) Appx 'C' : Para 1 (c) : The rooftop area where the work is to be undertaken will be for an area marked as rooftop area in the diagram attached as **Appendix D** to the RFP. The rates for the work will be quoted in the Commercial Bid Waterproofing of Rooftop Area and Parapet wall.

(f) Appx 'C' : Para 2 table heading. : **Quotes for Waterproofing of Rooftop Area and Parapet Wall**

2. However, the same was also amply clarified at page 4 : para 2(b), Appx 'B' and para 2 of Appx 'C'.

3. The same has got no implications or change to the RFP and should be construed only as clarifications.